

BLANK PAGE



IS: 11216 - 1985

Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

UDC 693:1:620:192:47:006:76



@ Copyright 1985

INDIAN STANDARDS INSTITUTION
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG
NEW DELHI 110002

Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

Dams (Overflow and Non-overflow) Sectional Committee, BDC 53

Chairman

SHRI V. B. Patel

Representing

Irrigation Department, Government of Gujarat, Gandhinagar

Members

SHRI R. K. BHASIN

SHRI J. S. KHURANA (Alternate)
PROF M. C. CHATURVEDI
CHIEF ENGINEER, THEIN DAM
DESIGN

DIRECTOR (DAM), THEIN DAM
DESIGN (Alternate)

SHRI C. ETTY DARWIN

SUPERINTENDING ENGINEER (DESIGNS) (Alternate)

DIRECTOR

JOINT DIRECTOR (Alternate)
DIRECTOR (E & RDD-I)

DEPUTY DIRECTOR (E & RDD-I) (Alternate)

SHRI M. V. S. IYENGAR

SHRIK. MADHAVAN

DIRECTOR (C & MDD-I) (Alternate)

OFFICER ON SPECIAL DUTY

SUPERINTENDING ENGINEER (DESIGNS) (Alternate) SHRI RAMABHADRAN NAIR SHRI T. RANGANNA

SHRIT, RANGANN. REPRESENTATIVE

SECRETARY

DIRECTOR (CIVIL) (Alternate)

Bhakra Beas Management Board, Nangal

Township
Indian Institute of Technology, New Delhi

Irrigation Department, Government of Punjab, Chandigarh

In personal capacity (P.O. Muttada, Trivandrum)
Public Works Department, Government of Tamil
Nadu, Madras

Central Water & Power Research Station, Pune

Central Water Commission, New Delhi

Hindustan Construction Co Ltd, Bombay Central Water Commission, New Delhi

Irrigation Department, Government of Andhra Pradesh, Hyderabad

Kerala State Electricity Board, Trivandrum Karnataka Power Corporation Limited, Bangalore Institution of Engineers (India), Calcutta Central Board of Irrigation & Power, New Delhi

(Continued on page 2)

© Copyright 1985 INDIAN STANDARDS INSTITUTION

This publication is protected under the Indian Copyright Act (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

TS: 11216 - 1985

(Continued from page 1)

Members

Representing

Gandhinagar

SUPERINTENDING ENGINEER

(CDO)

UNIT LEADER (C) (Alternate)

SUPERINTENDING ENGINEER (MD) CDO

SHRI G. RAMAN. Director (Civ Engg)

Department, Government Irrigation of Maharashtra, Bombay

Irrigation Department, Government of Gujarat,

Director General, ISI (Ex-officio Member)

Secretary

SHRI K. K. SHARMA Deputy Director (Civ Engg), ISI

Masonry and Concrete Dams Subcommittee, BDC 53:1

Convener

DR B. PANT

Water Resources Development Training Centre. Roorkee

Members

CHIEF ENGINEER ADDITIONAL (Designs)

DR B. M. AHUJA SHRIR, K. BHASIN

SHRI K. K. KHOSLA (Alternate)

CHIEF ENGINEER

OFFICER-ON-SPECIAL DUTY (Alternate)

SHBI C. ETTY DARWIN DIRECTOR (C & MDD-I) DEPUTY DIRECTOR (C & MDD-1) (Alternate)

DIRECTOR/PP (Alternate) DR A. K. MULLICK

SHRI N. K. JAIN (Alternate) SHRI RAMABHADRAN NAIR

SHRI M. P. BHARATHAN (Alternate) SHRI T. RANGANNA

SUPERINTENDING ENGINEER

Unit Leader (C) (Alternate) SUPERINTENDING ENGINEER (MD)

SHRIP, R. TONGONKAR

Irrigation Department, Government of Uttar Pradesh, Lucknow

Indian Institute of Technology, New Delhi Bhakra Beas Management Board, Nangal

Township

Irrigation Department, Government of Andhra Pradesh, Hyderabad

In personal capacity (P.O. Muttada, Trivandrum) Central Water Commission, New Delhi

DIRECTOR (TUNNEL & SPILLWAY) Irrigation Department, Government of Punjab. Chandigarh

Cement Research Institute of India, New Delhi

Kerala State Electricity Board, Trivandrum

Karnataka Power Corporation Ltd, Bangalore Irrigation Department, Government of Gujarat,

Gandhinagar

Irrigation & Power Department, Government of Maharashtra, Bombay

In personal capacity (Shirish Co-operative Housing Society, Bombay)

Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

O. FOREWORD

- 0.1 This Indian Standard was adopted by the Indian Standards Institution on 14 February 1985, after the draft finalized by the Dams (Overflow and Non-overflow) Sectional Committee had been approved by the Civil Engineering Division Council.
- 0.2 Masonry is being adopted as a standard material of construction for low as well as high gravity dams. One of the important characteristics of a construction material for water retaining structures is impermeability.
- 0.3 It is the common practice to specify the strength requirements of mortar in masonry dams. In addition, an upper limit of permeability for mortar and masonry in masonry dams is required to be specified with a view to achieving a standard of workmanship.
- 0.4 Varying standards have been used for testing masonry in various masonry dams with regard to their permeability. Hence a need was felt for rationalizing a standard criterion for the same.
- 0.5 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test, shall be rounded off in accordance with IS: 2-1960*. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

1. SCOPE

1.1 This code gives guidelines for permeability tests for masonry during and after construction and the standards to be achieved.

^{*}Rules for rounding off numerical values (revised).

IS 2 11216 - 1985

2. **DEFINITIONS**

- 2.1 Coefficient of Permeability The rate of flow of water under laminar flow conditions through a unit cross-sectional area of porous medium under a unit hydraulic gradient and at a standard temperature of 27°C.
- 2.2 Lugeons It is the water loss in litres per minute per metre depth of the drill hole under a pressure of 10 atmospheres maintained for 10 minutes in a drill hole of 46 to 76 mm diameter.

3. PERMEABILITY TESTS

3.1 Frequency of Test

- 3.1.1 Masonry Permeability test for the masonry shall be conducted regularly and at frequent intervals to judge quality and maintain uniformity. Every block, where fresh masonry is laid, shall be tested at least once every year.
- 3.1.2 Mortar Permeability tests on mortar shall normally be carried out once in a week. Specimens 100 mm dia and 50 mm high or similar size prepared from mortar as used on work shall be used for testing.
- 3.2 Testing Procedure for Masonry Test holes 76 mm in diameter and of appropriate depth (say 4 to 6 m) shall be drilled on the built up masonry after 28 days hardening. Drilling by rotary (diamond) drill shall be preferred in order to have the least disturbance of the masonry already constructed. The holes shall be kept 300 to 600 mm above the bottom level of the masonry to be tested. These holes shall be drilled vertically in two rows. One row shall be at 1.5 m from the axis of the dam. The second row shall be at about one-third of the width of the dam from the rear face excluding the front impervious face. The holes shall be provided staggered and it should be seen that at least one hole each in upstream and downstream portion in each block is provided. The holes may be closer if found necessary on the basis of the permeability test results. In locating the holes, position of any embedded parts, instruments, galleries and other opening shall be kept in view. The holes thus drilled shall be cleaned, filled with water and saturated for 48 hours. Then these holes shall be subjected to a water loss test to determine 'Lugeon' value. Notwithstanding the test pressures specified for lugeon values, the actual test pressures should not be so high as to cause disturbance to masonry. Then assuming linear variation of water loss with respect to the pressure applied, the water loss in lugeons may be interpreted. For details of procedure and test equipment reference may be made to IS: 5529 (Part 2)-1973*.

^{*}Code of practice for in-situ permeability tests: Part 2 Test in bedrock.

- 3.2.1 When a concrete membrane is used on the upstream face of a masonry dam, the upstream hole for water loss test shall be drilled one meter downstream of the junction of concrete membrane with masonry.
- 3.2.2 After the water loss tests the holes shall be grouted to refusal with neat cement and the results of grout intake recorded.
- 3.3 Testing Procedure for Mortar Permeability tests on mortar specimen shall be conducted in accordance with the procedure specified in IS: 1727-1967*.

4. STANDARDS OF IMPERMEABILITY

- 4.1 Masonry Standard of impermeability aimed at shall be a water loss of not more than 2.5 and 5 lugeons in the upstream and downstream portions of the dam respectively.
- 4.1.1 Permissible water loss in holes drilled in accordance with 3.2.1 shall be not more than 2.5 or 5 lugeons depending on the mortar mix used for masonry at that location (rich or lean respectively).
- 4.1.2 The values of water loss obtained from the test is the overall value of masonry including loss into cracks joints, etc. It provides an approximate estimate of the possible leakage that may take place through specific zones of masonry.
- **4.2 Mortar** Mortar as used on work shall not give a coefficient of permeability greater than 2.5×10^{-8} mm/s for rich mortar and 4.8×10^{-8} mm/s for lean mortar.

5. FACTORS AFFECTING PERMEABILITY

- 5.1 Two factors affecting permeability of the masonry are:
 - a) permeability of mortar itself; and
 - b) workmanship, namely, whether voids between the stones are filled with mortar or left free.
- 5.2 Pointing in the upstream face reduces seepage through the dam.

6. REMEDIAL MEASURES

6.1 If the test results indicate water loss greater than specified values grouting should be done as a remedial measure. Grouting pressure should be kept such that it does not damage the constructed masonry.

[&]quot;Methods of test for pozzolanic material (first revision).

INDIAN STANDARDS

ON

IS:

DAMS

6512-1984	Criteria for design of solid gravity dams (first revision)
69 55-1 973	Code of practice for subsurface exploration for earth and rockfill dams
7 8 94-1975	Code of practice for stability analysis of earth dams
8237-1976	Code of practice for protection of slope for reservoir embankments
8414-1977	Guidelines for design of under-seepage control measures for earth and rockfill dams
8605-1977	Code of practice for construction of masonry in dams

	Guidelines for design of large earth and rockfill dams								
9296-1979	Guidelines	for	inspection	and	maintenance	of	dams	and	appurtenant

9 2 9 7-19 79	Recommendations for lighting, ventilation and other facilities inside	dams
9429-1980	Code of practice for drainage system for earth and rockfill dams	

10135-1982 Code of practice for drainage system for gravity dams 10635-1983 Guidelines for free board requirement in embankment dams